

BRUHATH BANGALORE MAHANAGARA PALIKE, DASRAHALLI ZONE
Office Of The Executive Engineer, Dasarahalli Division
SCHEDULE-B

NAME OF THE WORK: Construction of RCC drain at Chikkasandra Govt.School Surrounding areas in Ward No.12, Shettyhalli Sub Division.

Sl No	Description Of Work	Unit	Qty	Rate To Be Quoted	
				In Figures (Rs)	In Words (Rs)
1	2	3	4	5	6
1	Earth work excavation by manual means in Hard soil involving an horizontal throw upto 2 metres and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications with all leads and lifts including Conveying the excavated earth silt, debris and over burden earth etc., to lead of 0 to 9 kms distance by using private vehicle this includes the cost of loading and unloading charges etc., complete as per the direction of Engineer-in-charge of the work (PWD SR 2016-17, Page No.142, Item No.19.2)	Cum	595.08	208.82	Rupees Two hundred and Eight And Eighty two Paise only
2	KSRB 4-1.3 : Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1.4.2 (PWD SR 2016-17 Page No.12, Item No. 4.3)	Cum	98.64	5159.02	Rupees Five Thousand one hundred and fifty nine And two Paise Only
3	KSRRB M2200-5.9. Design mix M20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.48 cum, with superplasticiser @3lts confirming to IS9103-1999 Reaffirmed-2008 -i) Upto 5m height (Pg.No.223, It.No.28.7.9)	Cum	248.67	6965.26	Rupees Six Thousand Nine Hundred And Sixty five And twenty six Paise Only
4	KSRRB M2200 Supplying, fitting and placing TMT bar Fe500 reinforcement in sub-structure complete as per drawing and Technical Specification complete as per specifications MORTH Specification No.1600 & 2200 (Pg.No. 17, I.No. 28.8.2)	Ton	12.43	74331.44	Rupees Seventy four Thousand three hundred and thirty one And Forty four Paise Only


EXECUTIVE ENGINEER-4
 Sr. Civil Engineer
 BENGALURU-560 010


 Executive Engineer
 Dasarahalli Division

5	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth cills and string courses cost of all materials, labour complete as per specifications. (Pg.No. 15, It.No.4.31)	Sqm	1638.60	310.58	Rupees Three hundred and ten and fifty Eight Paise Only
6	Supplying and fixing precast reinforced concrete slab 10 cm thick of mix M20 using 20mm and downsize graded granite metal using reinforcement 10 mm dia steel at 150mm c/c bothway cost, transportation, hire charges of machinery, machine cutting the vertical face to get plain even surface etc., Complete with all leads and lift conveyance charges, labour charges inclusive of cost of all materials- Data rate approved by Chief Engineer, Dasarahalli zone.	Sqm	444.60	1680.00	Rupees One thousand Six hundred and Eighty Only


 EXECUTIVE ENGINEER-4
 Dasarahalli Division
 BENGALURU-560 010


 Executive Engineer,
 Dasarahalli Division,